

ALVO SINGLE LEVER PULL OUT



TAP8319, TAP8336

07-23

Guarantee (UK only):

Your tap has the benefit of a comprehensive manufacturer's guarantee, details of which are shown on your Proof of Purchase Document. Any claim during the period of the guarantee must be accompanied by the Proof of Purchase. The product must be correctly installed and operated in accordance with the manufacturer's instructions and used for normal domestic purposes. This guarantee does not cover accidental damage, misuse or alterations which are likely to affect the product. The guarantee is invalid if the product is tampered with or repaired by any unauthorised person. The guarantee in no way affects your statutory or legal rights.

Care Instructions for your Kitchen Sink Mixer:

To maintain the appearance of this tap, ensure that it is regularly cleaned only using a clean, soft damp cloth. A solution of warm water and a mild liquid detergent may be used where necessary, and then the fitting rinsed thoroughly and wiped dry. Any other cleaning action will invalidate your warranty.

Abrasive cleaners, scouring cleaners and acidic cleaners **must not be used** under any circumstances. Avoid contact with all solvents (including chlorinated solvents, ketones or acetones as these may result in surface deterioration or etching). Also avoid contact with any harsh household chemicals such as oven cleaners, drain cleaners, rust removers, paint strippers and toilet bowl cleaners, bar keepers friend or Brasso.

Where the tap has a removable aerator on the spout exit it can be removed and cleaned periodically to maintain optimum flow performance.

Important Technical Data:

Minimum operating pressure: 1.2 bar
Maximum operating pressure: 5.5 bar*
Flow characteristics: Single flow

Maximum hot water temperature: 70°C*
Recommended hot water temperature: 46°C

*If these temperatures or pressures are exceeded, even for short periods, damage can result. In these instances, a thermostatic mixing or pressure reducing valve should be installed.

This product is manufactured in accordance with recognised European standards. Please ensure that your Kitchen mixer is fitted in accordance with Local Water Byelaws. Where hot and cold water mix within the mixertap, then suitable non return (check) valves should be installed to the hot and cold supplies to prevent backflow.

Hot and cold supply pressures should be as closely balanced as possible for best results. Supply pipes should maintain the maximum diameter until immediately before the fitting. The differential between the hot and cold water supply temperatures should be sufficient to allow correct mixing function.

These installation guidelines have been prepared for your direction and you must exercise due care at all times. We do not accept responsibility for problems that may occur through improper installation. Whilst assembling the tap take care not to accidentally loosen any factory fixed assemblies.

This tap has been 100% assembly tested; therefore, you may expect a small residual amount of water to remain in the tap when delivered. Any water marks can be removed using the above care advice.

Installation Preparation:

All parts should be removed from their packaging and inspected for completeness and transport damage prior to installation.

Before installing the new mixer, **it is essential that you thoroughly flush through the supply pipes** in order to remove any remaining solder, swarf or impurities from your system. Failure to carry out this simple procedure could cause problems or damage to the workings of the mixertap and invalidate the warranty.

We recommend installing isolation valves and particle (mesh) filters to both the hot and cold feed pipes in an accessible position. This will help to prevent premature failure of the valves and ease any future maintenance.

Shut off the water heating system and ensure that the mains stopcock is closed. Ensure both the hot and cold water supplies are isolated before commencing installation.


This mixertap requires a $\varnothing 35\text{mm}$ tap hole, if replacing an existing tap, remove the tap & clean the end of the feed pipes using wire wool, the tap hole area should be free from dirt and sealant. You should ensure that the product will both fit into the depth of the mounting surface available and reach the required outlet positions before installation.

Loosely position the tap and tail pipes to check if any alteration to the existing pipework is required, if this is the case do this now.

Where this product is supplied with flexible inlet hoses you must follow the additional guidelines supplied for their correct installation.

Installation:

1. Place the upper seal (B) into the base of the tap (A).
2. Screw the hot & cold water tail pipes (N & O) into the base of the tap (A) as shown, note the cold flexible hose inserts towards the rear of the tap as shown on the diagram.
3. Place the mixer tap (A), upper seal (B) and fixing stud (C) onto the sink/worktop, passing the tail pipes (N & O) and the pull out hose (K) through the tap hole.
4. Pass the rubber horseshoe (E) and the metal horseshoe (F) over the fixing stud (C) around the flexible tail pipes (N & O) and the pull out hose (K). Note: only if fitting the tap to a stainless steel sink, the white triangular stabiliser (D) can be placed where shown to help stabilise the weight of the tap.
5. Fasten fixing nut (G) securely onto the fixing stud (C) to fix the tap (A) into its correct location.
6. Place fiber washer (H) into the top of adaptor nut (I), now screw the adaptor nut (I) onto the fixing stud (C).
7. Place fiber washer (J) into the bottom of adaptor nut (I), now using a spanner screw the pull-out pipe hose (K) into the adaptor nut (I).
8. Fix the hose weight (L) with screws (M) just before the lowest point of pull out hose (K) as shown.
9. Connect the hot and cold tail pipes (N & O) to the water mains using $\frac{1}{2}$ " BSPx15mm compression fittings.



Key:	Description:	Qty.
A	Mixer body	1
B	Base plinth	1
C	Upper seal	1
D	fixing stud / mixed water outlet	1
E	Triangular stabilising bracket	1
F	Lower gasket	1
G	Metal horseshoe	1
H	Fixing nut	1
I	Fibre seal	1
J	Adaptor nut	1
K	Fibre seal	1
L	Hose weight	1
M	Hose weight screws	2
N	Mixed water outlet hose	1
O	Hot Flexi tail	1
P	Cold Flexi tail	1

After installation:

Once you have visually checked the installation of the new tap and all connections, ensure that all other fittings are closed except the new tap which should be left open.

Turn on your water heating system and ensure that your mains stopcock is open. Reconnect both the hot and cold water supplies to this fitting.

Check the function of flow and function of hot, cold and mixed water.







Turn off the tap and check carefully for any leaks around all connections on the fitting and adjoining plumbing. If possible, return to the installation after a longer period to double check for slower leaks. If pressure testing equipment is available check the installation to the maximum recommended pressure.

Clean the tap to remove any marks created during installation as instructed then place a bag over the product to protect the tap until it is ready for use.

The installation should be periodically checked for damage, if the property is left unattended for a prolonged period, we recommend isolating water supplies.

Correct use of flexible hose connectors

This product is supplied with flexible hose connections for ease of fitting, failure to observe these standard installation guidelines will invalidate the warranty for your product.



- Before assembling the hose to the product ensure the hose has been crimped (as highlighted) on both ends of the hose after the braided casing.
- Always screw the flexi hoses into the product only by hand until feeling mechanical rest, a spanner must not be used on the product connecting end of the hose.
- Always use the pipes provided.
- Never twist or stretch the flexible hose during installation.
- Do not overtighten the hexagonal end of the hose when using a spanner causing the hose to twist.
- The braiding on the flexible hose must not be in contact with any scarcely aggressive chemicals, internal or external room walls or dissimilar metals or materials.
- Observe the minimum bend radius of 50mm, hoses must not be kinked or looped.
- Hoses must not be double bent in multiple directions.
- Both ends of the hose must have a minimum 50mm straight section before any bend.

